






USDA FOREST PRODUCTS LABORATORY 8' x 8' WOOD TORNADO SHELTER



CONCEPT, DESIGN, AND TESTING BY ROBERT H. FALK, PhD, PE
OF FOREST PRODUCTS LABORATORY

CONSTRUCTION DRAWINGS PREPARED BY LUIS ROMEO ESCOBAR
OF HOME INNOVATION RESEARCH LABS

PAGE 2 GENERAL NOTES

THESE CONSTRUCTION DRAWINGS REPRESENT THE FINISHED STRUCTURE. CONSTRUCTION MEANS AND METHODS CAN BE FOUND IN THE CONSTRUCTION GUIDE.

THE BUILDER SHALL PROVIDE WEATHER PROTECTION TO THE STRUCTURE DURING CONSTRUCTION.

IF THERE IS A CONFLICT AMONG THE CONSTRUCTION GUIDE, GENERAL NOTES, SPECIFICATIONS, AND PLANS, THE MORE STRINGENT CRITERIA SHALL APPLY.

THE BUILDER SHALL BE RESPONSIBLE FOR VERIFICATION AND COORDINATION OF ALL DIMENSIONS, CONDITIONS, AND ELEVATIONS.

COMPLETE INSPECTION REQUIREMENTS SHALL BE AS DIRECTED BY THE LOCAL BUILDING DEPARTMENT.

THE CONSTRUCTION DRAWINGS SHALL NOT BE SCALED.

FOLLOW MANUFACTURER'S RECOMMENDATIONS FOR INSTALLATION OF UPLIFT/SHEAR RESISTANCE CONNECTORS.

FOR ALL CONSTRUCTION, USE ONLY SCREWS AND HARDWARE THAT HAVE BEEN EVALUATED THROUGH AN ANSI-APPROVED PRODUCT CERTIFICATION BODY SUCH AS IAPMO-OES OR ICC-ES.

VENTILATION IS TO BE PROVIDED PER PLAN DETAILS.

MAXIMUM WALL HEIGHT FOR SHELTER SHALL BE 8'-0".

PAGE 3 BEAMS CONSTRUCTION



EACH BEAM MADE BY NAILING AND GLUING THREE 2x8s.

TWO ROWS OF 16D NAILS SPACED 11" OC ALONG LENGTH OF 2x8s BOARDS.


MIDDLE BEAM OFFSET 1.5" TO CREATE TONGUE-AND-GROOVE CROSS-SECTION.

TWO BEADS OF CONSTRUCTION ADHESIVE ALONG LENGTH OF BOARDS FOR ADDED STRENGTH.

4.5" NOTCH CUT OUT OF ENDS OF SOME BEAMS SO THEY OVERLAP AT CORNERS IN LOG-CABIN STYLE.



ENTRANCE WALL (USED AS EXAMPLE)



CONSTRUCTION ADHESIVE APPLIED TO INSIDE FACES OF BEAM GROOVES AS WALL BEAMS ARE STACKED ONE COURSE ON TOP OF PREVIOUS.

HAMMER BEAMS DOWN TO ENSURE A TIGHT FIT AND FLAT TOP.


ENTRANCE HEADER AND JAMBS INSTALLED WITH 16D NAILS.

ROOF BEAMS INSTALLED FROM LEFT TO RIGHT.

ROOF BEAMS ATTACHED TO WALLS BY DRIVING 8" LONG WOOD SCREWS UP AT 45 DEGREE ANGLES THROUGH WALLS BELOW.

OBSERVE SCREW SCHEDULE IN DIAGRAMS.


ROOF PANEL




PAGE 4 WALL AND ROOF BEAMS

LEFT AND RIGHT WALL:
14 SCREWS SPACED 7" OC ALONG
FULL LENGTH OF WALL USED TO
SECURE FIRST AND FINAL ROOF
BEAMS TO WALLS BELOW


LEFT WALL



ENTRANCE WALL



RIGHT WALL




FULL HEIGHT OF
ROOM 90.75"
(INCLUDING
PRESERVATIVE
TREATED BASE
BOARDS)

WALLS REST ON A BASE
OF PRESERVATIVE
TREATED 1x6 BOARDS

FINAL ROOF BEAM
TWO SCREWS USED TO SECURE
THIS BEAM TO WALL BELOW

ENTRANCE AND BACK WALL:
ONE SCREW PER ROOF BEAM
FOR FIRST 12 BEAMS
SCREWS SPACED 7.25" OC
DRIVEN UP AT 45 DEGREE
ANGLE THROUGH WALL
BELOW

BACK WALL




ENTRANCE HEADER AND
JAMBS MADE FROM 2x6
BOARDS RIP-CUT TO
MATCH WALL THICKNESS


EVERY CORNER
REINFORCED WITH
TWO 8" LONG WOOD
SCREWS

BEAMS INSTALLED BY
STACKING ONE
COURSE ON TOP OF
THE PREVIOUS
COURSE;
CORNERS OVERLAP IN
LOG CABIN MANNER


INTERIOR SHEATHING - ENTRANCE WALL




INTERIOR SHEATHING - LEFT, RIGHT, BACK WALL



EXTERIOR SHEATHING - ENTRANCE WALL



EXTERIOR SHEATHING - LEFT, RIGHT, BACK WALL



PAGE 5 SHEATHING

INTERIOR AND EXTERIOR 23/32 PLYWOOD SHEATHING.

TWO SHEETS PER WALL, TWO SHEETS FOR INTERIOR CEILING.

CUT PLYWOOD SHEETS TO FIT ACTUAL WALL DIMENSIONS.



SHEATHING ON INTERIOR AND EXTERIOR ENTRANCE WALL MUST BE CUT TO ACCOMMODATE 36"x79" ENTRANCE OPENING.

CONSTRUCTION ADHESIVE AND 16D NAILS USED TO ATTACH SHEATHING TO WALLS.

OBSERVE NAILING PATTERN SHOWN; NOTE: TWO ROWS OF NAILS SPACED 3" OC AT CEILING BEAMS FOR EXTERIOR.

REINFORCING ENTRANCE HEADER/JAMB ANGLES -
VIEW FROM ROOM INTERIOR

PAGE 6 ENTRANCE REINFORCEMENT



CUSTOM-MADE REINFORCEMENT
ANGLES INSTALLED AT ROOM
ENTRANCE.




14 GAUGE STEEL; L-SHAPE WITH 90
DEGREE BEND.

HEADER ANGLE INSTALLED FIRST;
LEFT AND RIGHT JAMB ANGLES
OVERLAP.

3" LAG BOLTS SPACED 12" OC
ALONG LENGTH ON ROOM
INTERIOR ON JAMB (WALL
THICKNESS) FOR JAMB ANGLES.

3" LAG BOLTS SPACED 10" OC
ALONG LENGTH ON HEADER
ANGLE.

FIELD DRILL HOLE WHERE JAMB
ANGLES OVERLAP HEADER ANGLE.




FIVE LAYERS OF DOOR HELD TOGETHER WITH 15 BOLTS, 3/8" DIAMETER, 2-1/2" LONG; WASHERS ON EXTERIOR AND INTERIOR


BOLTS SPACED 19" OC VERTICALLY AND 17" OC HORIZONTALLY

PAGE 7 DOOR BUILD




DOOR MOUNTING HARDWARE -
VIEW FROM ROOM EXTERIOR




DOOR LOCKING HARDWARE -
VIEW FROM ROOM INTERIOR



PAGE 8 DOOR HARDWARE




3/8" DIAMETER BOLTS
SECURE STRAP HINGE TO
DOOR EXTERIOR
ONE BOLT IN TWO HOLES
FURTHEST FROM BOLT HOOK




LOCKING MECHANISM DETAIL: SLIDE BOLT
INSTALLED OVER 2x4 DOOR LATCH OFFSET

TWO 3/8" DIAMETER BOLTS USED TO INSTALL EACH
SLIDE BOLT ON 2x4 DOOR LATCH OFFSET AND
THROUGH DOOR

FRONT WALL - NO VENTILATION HOLES




RIGHT WALL - VENTILATION HOLES




VENTILATION PROVIDED BY 24 HOLES, 1" DIAMETER

TWELVE HOLES ON WALL TO RIGHT OF ENTRANCE WALL LOCATED 1' FROM TOP OF WALL; HOLES SPACED 7" OC

BACK WALL - NO VENTILATION HOLES




LEFT WALL - VENTILATION HOLES



TWELVE HOLES ON WALL TO LEFT OF ENTRANCE WALL ARE LOCATED 2' FROM BOTTOM OF WALL; HOLES SPACED 7" OC


PAGE 9
VENTILATION

ENTRANCE WALL




TENSION TIES:
SIMPSON
STRONG TIE
HTT5

DETAIL: CONCRETE ANCHOR
SIMPSON STRONG TIE HTT5



FOLLOW ANCHOR
MANUFACTURER'S
INSTALLATION
INSTRUCTIONS
REGARDING FASTENERS
CONNECTION TO SLAB
MADE BY INSTALLING $\frac{5}{8}$ "
DIAMETER ANCHOR STUD
IN EACH TENSION TIE
AND SEALING WITH
ANCHOR EPOXY

PAGE 10
ANCHORING



16 TENSION TIES
ANCHOR THE
SHELTER'S
WALLS TO THE
CONCRETE SLAB

4 TENSION TIES
PER WALL

AERIAL VIEW

DOOR

CONCRETE SLAB MUST EXTEND 5' (60") ON EACH SIDE
OF SHELTER AT MINIMUM
FOUNDATION MUST BE 4" THICK AT MINIMUM WITH
4000 PSI MIN STRENGTH
6X6-W1.4xW1.4 WELDED WIRE REINFORCEMENT OVER
ENTIRE AREA OR 4 BARS AT MAX SPACING OF 18" OC
IN TWO PERPENDICULAR DIRECTIONS

RIGHT SIDE WALL

